


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

25-27-8E

Company- BEAUMONT PETROLEUM COMPANY
Farm- Lewis "A" No. 35

SEC. 25 T. 27 R. 8E
SW NE SW
1630' fr. S Line
1670' fr. W Line
County Greenwood
KANSAS

Total Depth. 2799'
Comm. 5-4-54 Comp. 6-2-54
Shot or Treated.
Contractor.
Issued. 11-3-56



Elevation. 1428' RB

Production. 25 BOPD

CASING:

103/4" @35' w/40 sx cem.
7" @2799' w/200 sx cem.

Figures indicate Bottom of Formations.

	ROTARY BUSHING 4"8 ABOVE GROUND LEVEL
cellar	5
lime shale	170
shale-lime strks	500
lime	580
shale shelss	625
shale lime strks	1340
lime	1540
shale	1675
lime	1840
sdv shale	1876
shale lime strks	2095
lime	2145
lime shale	2220
shale lime strks	2423
lime	2580
lime shale	2665
lime	2695
shale	2744
lime	2799 RTD
Total Depth	

TOPS:

Kansas City	1665
Base/Kansas City	1821
Marmaton	1971
Chero	2157
Mississippi Lime	2423
Kinderhook Shale	2635
Arbuckle Dolomite	2744