

FRED FRANK  
Meyrick No. 3.


23 -11-238 *Plott*

SEC. 23 T. 11 R. 23E  
NE NW SE

OCT 23 1937

Total Depth. 555'  
Comm. 3-2-30 Comp. 3-17-30  
Shot or Treated.  
Contractor.  
Issued. 10-23-37

County. Wyandotte.



CASING:

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

|                     |           |
|---------------------|-----------|
| soil                | 3         |
| lime                | 11 - L    |
| shale               | 40        |
| lime                | 49        |
| shale               | 53        |
| lime                | 61        |
| shale               | 73        |
| lime                | 91        |
| shale               | 97        |
| lime little wtr     | 99        |
| sand                | 104       |
| shale               | 127       |
| lime                | 140       |
| shale blk           | 147       |
| lime                | 162       |
| shale wh            | 165       |
| shale blk           | 170       |
| lime                | 180       |
| shale grey          | 193       |
| lime                | 195       |
| limo sdy            | 210       |
| shale               | 214       |
| lime                | 229       |
| shale sdy wtr & gas | 231       |
| lime                | 258       |
| shale               | 263       |
| lime                | 272 - BRC |
| shale               | 290       |
| sand gas show       | 292       |
| shale               | 311       |
| sdv lime            | 313       |
| shale sdy           | 376       |
| sand gas            | 394       |
| shale green         | 396       |
| red rock            | 411       |
| shale green         | 423       |
| lime                | 425 - ch  |
| shale               | 439       |
| sand limey          | 448       |
| shale grey          | 457       |
| lime                | 461       |
| sand oil show       | 465       |
| shale               | 480       |
| lime                | 484       |
| shale               | 488       |

|              |     |
|--------------|-----|
| lime         | 493 |
| shale grey   | 510 |
| shale drk    | 520 |
| shale grey   | 535 |
| sand         | 550 |
| shale        | 555 |
| Total Depth. |     |