

2-11-24E Plotted
9.8.8.


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg, Wichita, Kansas.

RUF AND SONS
Conner Estate No. 1.

SEC. 2 T. 11 R. 24E.
NW SW NE SW
1960' fr SL 1520' fr WL
NE $\frac{1}{4}$ SW $\frac{1}{4}$

Total Depth. 452
Comm. 7-19-33 Comp. 7-24-33
Shot or Treated.
Contractor.
Issued. 5-13-39

County Wyandotte



CASING.

6 $\frac{1}{2}$ " 305'

Elevation.

Production. DRY

Figures Indicate Bottom of Formations.

soil	21	limo	364
gravel and boulders	26	shale blk gas	367
lime Drum	39	sand	373
shale	55	sand hard	376 oil show.
lime	57	shale	393 total gaugo 82,680
shale	60	lime	395
lime	62	shale blk	398
shale	69	shale	405
lime Winterset	95	lime	406
shale blkish good gas	100	shale	411
lime Bethany Falls	120	limo	415
shale some blk	123	shale blk	417
lime	125	sand hard from 423-	425
shale	128	sand	430 116,400 in hole
SLM 137 $\frac{1}{2}$ was 135 by strings.		sand oil show	452
lime Hertha	139		
shale	210	Total Depth.	
sand	215		
shale sdy	245		
sand and lime shells	250		
shale sdy	253		
shale green sticky	258		
red bed	260		
shale	266		
lime sdy	270		
shale	286		
limo hard	287		
shale	295		
limo	299		
shale SLM 306 OK	300		
sand hard	308		
sand gas bubbles	310		
sand Oil show 12,000 gas	325		
shale	334		
lime	338		
sand gas	349		
entiro gaugo at 350'	44,000		
shale dark	360		