

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas

3-11-24E
K. L. O'NEILL
9.2.1


RUF ET AL.
Youngmans No. 2

SEC 3 T. 11 R. 24E.
SW NE NE NE

25' No. of Youngmans No. 1

Total Depth. 735
Comm. 5-10-37 Comp. 5-17-37
Shot or Treated.
Contractor.
Issued. 4-29-39

County Wyandotte.



CASING.

65/8" 472'
47/8" 672'

Elevation

Production. 260,640 G.
R.P. 238 #

Figures Indicate Bottom of Formations.

soil and yellow	25	lime Peru Cap RIM 433 $\frac{1}{2}$	436
sand soft	30	sand	444
lime Iola	52	little gas increase	
shale grey	87	shale	455
RIM 65		shale blk salt water too	
lime	97	much to carry	463
Raytown		sand hard	469
shale green and some		hole caving bad was still	
red bed	113	dumping shale	492
lime Cement City	123	lime	494
shale	128	shale dark	511
lime Drum	138	sdv limo	515
shale muddy	155	shale dark	516
lime	157	gas bubbles	516
shale	159	sand broken 20,000 G.	535
lime	163	water and Oil show 535 ft	
shale dark	166	sand more water	595
lime Upper Winterset	177	water increased	
shale	178	water increased with depth.	
lime hard lower		shale	606
Winterset	196	lime	608
shale	200	shale	616
lime Bethany Falls	221	lime	620
shale dark	223	shale dark	660
lime	224	shale dark	686
shale	225	shale	687
lime Hertha RIM	238	shale dark	715
shale green	243	shale light some	
shale grey	255	sand	720
shale dark	355	shale dark sticky	729
shale and little		above shale cuttings had	
red bed	360	some pyrite of iron bubbles	
sdv shale	367	at 729	
lime	368	sand gas 31,000	730
shale sdv with sand		sand gas 200,000	734
seams	381	sand gas 260,000	735
sdv lime gas show	384	Total Depth.	
shale	390		
lime	394		
shale	398		
sand and shale			
seams	400		
shale white	407		
sand 20,000 G.	415		
sand 57,000 G.	423		
shale	429		