

10 - 11 - 248


Company
Farm Joe Steinegar No. 1

Sec. 10 T. 11 R. 24 E
Loc. NE 1/4 SW 1/4

*Plotted
ACW*

Total Depth 502
Comm. 8/3/33 Comp. 8/9/33
Shot or Treated
Contractor
Issued

County Wyandotte



Casing
20 in. 10 in.
15 1/2 8 1/4
12 1/2 6 5/8 6 1/4" --116
13 3/8 5 3/16 4 7/8" --427

Elevation 877 (U.S. tie possibly 887)

Production Dry & Ab'd

Figures Indicate Bottom of Formation

clay	30	
river gravel	45	hit good sweet water well
water sand	66	
river mud & gravel	116	
lime hard	144	
shale	149	
lime	170	
shale dark	173	
lime	175	
shale	177	
lime (Hertha)	187	run steel line at 190 ft.
shale	319	
red bed & shale green	323	
shale	352	
lime sandy	362	
sand	370	show of oil & gas
shale	391	
lime	401	
shale	418	
lime	422	
shale black	427	
sand	435	gas show
shale	456	
lime	458	run steel line 460 ft. OK
shale dark	469	gas bubbles from 458 to 465
lime hard	471	
shale	474	
lime	482	
slate black or coal	490	
sand broken	502	

T.D.

This well was plugged by Geol. White, official plugger, Aug. 11, 1933