

15-11-24E


Plotted
Now

SUBURBAN GAS CO.
Simpson No. 1.

SEC. 15 T. 11 R. 24 E
Cen SW $\frac{1}{4}$

Total Depth. 401'
Comm. 11-14-41 Comp. 11-25-41
Shot or Treated.
Contractor. W.L.Hendee
Issued. 9-18-43

County. Wyandotte



CASING:

Elevation.

Production. 20,000 G.
(Now dead)

Figures Indicate Bottom of Formations.

soil	5
sdv clay	47
lime brkn	54
shale	56
lime	58
shale	60
lime hd	70
shale dk wtr	72
lime	73
shale lgt	80
lime	97
shale	101
lime	103
shale dk	106
lime	114
shale	115
lime Hertha	117
106-117	
shale gy	157
sand	170
shale gy	220
shale wh	232
shale red	234
shale lgt	243
lime	245
shale wh	???
lime	269
shale sdv gy	273
sand hd	279
shale gy	287
sand oil show <i>Bandevn</i>	292
shale wh	307
lime sdv	316
shale gy	334
lime	337
shale blk, gas bubble	339
sand oil <i>Perm</i>	355
sand hd	358
white shale green	371
shale dk	374
lime	376
slate blk, gas bubble	377
shale gy	386
lime	388
shale gy	394
sand	401
Total Depth.	