


Plotted new
17-11-24E

HAAS-HENDEE & SON
Melville No. 1.

SEC. 17 T. 11 R. 24 E
NEc SE

Total Depth. 400'
Comm. 7-28-42 Comp. 8-1-42
Shot or Treated.
Contractor, Hendee
Issued. 11-27-43

County, Wyandotte



CASING:

4 7/8" 232'

Elevation.

Production, 10,000 Gas

Figures Indicate Bottom of Formations.

clay	22
lime	34
shale gy	35
lime	39
shale gy sdy	58
sand	67
shale gy	79
lime sdy	84
slate blk	88
lime	89
shale gy	90
lime	91
shale gy sdy	99
lime	111
shale dk sdy	117
lime	122
shale gy	124
lime	128
shale	129
lime	133
shale	142
lime	143
shale dk	145
lime	148
shale gy	153
lime sdy	163
shale	164
lime	170
shale	171
lime	181
slate blk wtr	184
shale gy	186
lime	206
slate blk	210
lime	211
shale gy	215
lime sdy	223
shale lgt sdy	232
lime sdy	235
sdv gas Knobtown	249
shale gy sdy	260
shale gy	273
shale gy sdy	306
shale gy	318
shale gy sdy	327
shale lgt	332
shale lgt sdy	336
sand	344
shale blk	346
red bed	353
lime sdy	362
shale green	374
lime sdy	377
shale green	384
lime sdy	388
lime lgt	390
lime	393
shale lgt	395
sand oil	400 Total Depth.