

24-11-246


FRED FRANK
Hall No. 4

SEC. 24 T. 11 R. 24E.
NW 1/4 SW

Total Depth. 573
Comm. 3-9-30 Comp. 3-16-30
Shot or Treated.
Contractor.
Issued. 12-18-37

County Wyandotte

DEC 18 1937



CASING.

65/8" 89'

Elevation. 844

Production. DRY.

Figures Indicate Bottom of Formations.

soil	10	shale	446
clay	30 wtr	lime	449
sand	48	shale grey	455
lime	54	sand	464 gas
sand little water	70	shale sdy	480
lime	83	shale blue	498
sand	90	shale dark	505
lime white	108	shale dark sdy	535
shale limey	115	shale blk	549
lime	118	lime	553
shale	125	shale grey	562
lime	129	sand	567
sand	135 oil, show	shale grey	573
lime	153	Total Depth.	
shale limey	155		
lime	175		
shale blk	180		
Gas bubbles and water			
lime	195		
shale grey	201		
shale and grey sdy	232		
sand	235		
shale sdy	295		
shale	306		
sand	314 gas.		
shale red	320		
shale grey	345		
lime grey	350		
sand	355		
oil show			
sand	360		
shale	376		
lime broken	385		
shale grey	395		
shale dark	404		
lime	408		
shale grey sdy	435		
lime	437		
shale blue	440		
lime	442		