

Plotted *Prum* 18-11-24E

Company Green

Sec. 18 T. 11 R. 24 E

Farm Shirwan

No. 2

Loc. SEc SE

100 ft. N. of #1

Total Depth 417 ?

County Wyandotte

Comm.

Comp.

Shot or Treated Acidized 600 gal. 397 to bottom

Contractor F. A. Cullum

hole

Issued

Casing

20 in.	10 in.
15 1/2	8 1/4
12 1/2	6 5/8
13 3/8	5 3/16

Elevation

Production

Figures Indicate Bottom of Formation

surface	10	
lime hard	20	
shale blue	26	
lime hard	30	
shale	32	
lime	40	
shale	48	
lime hard	78	Winterset
shale gray	83	
lime gray	98	
shale	103	
lime gray	112	Bethany Falls
shale gray	223	
red rock	226	
light shale	260	
brkn lime	270	
sand Oil show	287	Knobtown
shale gray	295	
lime hard	302	
shale	319	
hard lime	330	
shale	352	
med. lime	356	
limy shale	377	
sdv shale	390	
fine sand	392 1/2	Gas show
Oil show	417 ?	

Total Depth 417 ?