

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- McNEISH & GRALAPP
Farm- Miller No. 1

SEC. 12 T. 32 R. 5E
NW NW SW

Total Depth. 3072'
Comm. 12-31-52 Comp. 1-11-53
Shot or Treated.
Contractor. Watson Drlg. Co. Inc.
Issued. 3-14-53

County Cowley
KANSAS

Elevation. 1328
1330

Production. Pumps 25 Bbls.
plus 8 water

Figures indicate Bottom of Formations.

lime, shale	50
lime	155
lime, shale	580
shale, shells	810
shale, lime	1225
lime, shale	1485
shale, lime	1630
shale, lime streaks	1665
lime, shale	1755
sand, shale	1799
shale, lime	1875
lime	1879
shale	1907
sand, shale	1995
shale	2075
lime, shale	2126
shale	2349
sand	2357
sand, shale	2425
shale	2462
lime	2573
lime, shale	2650
shale, lime	2697
lime	2723
shale, lime streaks	2746
lime	2876
shale, lime streaks	2905
shale, sand streaks	2912
slight odor at	2905-2910
shale	2989
shale, sand	3030
Coring #1	3030-3060
saturated from	3042-3060
lost 10' of core #1	
Core #2 shale	3061-3067
Lost 3' of core #2	
shale	3069
chert, lime	3072
Total Depth	

Tops-Scout
Layton sand 2354
Bartlesville sand 3014
Mississippi lime 3075

Perforated (48 shots) 1-27-53 3054½ to 3046½ ft.
Sand frac 1-28-53
Started pumping 1-29-53