

Plotted 3-11-25E
ES.

Company

Sec. 3 T. 11 R. 25

Farm

No.

Loc. 723 T court St.
Kansas City, Kansas

Total Depth

County


Comm. 3-3-31

Comp.

Shot or Treated

Contractor R.M.C. Dilling Co.

Issued



Casing

20 in.	10 in.	
15 1-2	8 1-4	72'
12 1-2	6 5-8	258'
13 3-8	5 3-16	

Elevation

Production

4 7/8 518 1/2 - 569
Figures Indicate Bottom of Formation

Soil	3'	Shale	578
Clay	60	Set 4 7/8 at 569	
Shale blue water	72	Sand gas very small	581
Lime	82	Shale brown	615
Shale gray	86	Sand - little water	625
Lime	106	Shale	635
Shale black	108	Sand	666 1/2
Lime	112	Shale	671 1/2
Shale black	114	Sand - little gas	702
Lime	124	Shale	720
Sgale blue	150	Sand	735
Shale gray	260		
Lime	285		
reamed under 6 1/4 at 301 1/2'			
Sand - oil show	290		
Shale gray	318		
Set packer at 296			
Sand - gas	324		
Shale gray	327		
Lime sandy	331	set 6 1/4 350' Screwn packer	
Sand	340		
Lime	344		
Shale light	360		
Lime	363	set drip packer at 569	
Shale gray	364		
Lime	367		
Shale black	370	set blimy packer at 378	
Shale light	380		
Lime	385		
Shale black	395	Set 518 1/2 feet 4-7/8	
Shale gray	425		
Sand	480	oil showing & gas SLM 451	
Shale	495	Water at 445 ' to -	
Lime	499		
Shale gray	538		