


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas

Company- **BEAUMONT PETROLEUM COMPANY**
 Farm- **P. A. Miller** No. **1**

SEC. **13** T. **32** R. **5E**
 NW NW NE

Total Depth. **3588**
 Comm. **9-30-55** Comp. **11-2-55**
 Shot or Treated.
 Contractor.
 Issued. **8-4-56**

County **Cowley**
KANSAS



CASING:

8 5/8" **89'** cem w/ **75** sx
5 1/2" **3500'** cem w/ **25** sx.

Elevation. **1298**

Production. **25** BOPD

Figures indicate Bottom of Formations.
ROTARY BUSHING 5.5' ABOVE
GROUND LEVEL

| | |
|-------------------|----------|
| cellar | 5 |
| soil | 12 |
| lime | 85 |
| lime, shale brks | 550 |
| shale, lime strks | 1050 |
| lime, shale brks | 1280 |
| lime, shale strks | 1475 |
| shale, lime strks | 1705 |
| lime, shale brks | 1750 |
| sand, shale | 2040 |
| lime | 2102 |
| shale | 2229 |
| shale sdy | 2271 |
| sand | 2387 |
| shale | 2438 |
| lime | 2550 |
| shale | 2644 |
| lime, shale brks | 2770 |
| shale | 2930 |
| sand | 2977 |
| sand shale | 3036 |
| lime | 3429 |
| shale | 3496 |
| dolomite | RTD 3588 |
| Total Depth | |

Tops: **Scout**
 Layton sand 2266
 Base Layton Sand 2389
 Kansas City lime 2443
 Base K. C. 2557
 Marmaton 2658
 Cherokee 2775
 Bartlesville sand 2965
 Base Bart. Sand 3029
 Miss. lime 3041
 Arbuckle 3495

RTD 3588
 CTD dolomite 3468 LW