

4-11-25 *Plotted*

Company

Sec. 4 T. 11 R. 25

Farm Durant

No. 1

Loc.
12th St. & Garfield Ave.,
Kansas City, Kansas.
County Wyandotte

Total Depth 758'


Comm. 2-26-32

Comp.

Shot or Treated

Contractor C. E. Wyatt

Issued



Casing

20 in.	10 in.	
15 1-2	8 1-4	
12 1-2	6 5-8	117'
13 3-8	5 3-16	310.6'

Elevation 858 *295*

Production

Figures Indicate Bottom of Formation

Soil	3'	Gray shale	448
Clay sandy	70	Sand- oil & lots water	514
finer sand	115	Lime	516
Lime	124	Black slate	519
Dark shale	127	Lime	521
Lime	131	Sand - light gas SLM	522 539
Dark shale	134	Black slate	542
Lime-Hertha	141	Gray shale	552
Gray shale	250	Sand little gas	547 558
Sandy shale	265	Sandy shale	570
Red bed	272	Lime	571
Light sandy shale	285	Dark shale	579
Dark gray shale muddy	300	Black slate	581
Lime	302	Light shale	595
Gray shale	312	lime	596
Lime	319	Gray shale	607
Gray shale	325	Black slate	610
Sand (Peru)	332	Dark shale	620
Dark shale	337	Gray sandy shale	627
Black slate-gas bubbles	339	Dark shale	633
Lime	346	Black slate	644
Dark shale	364	Sand - gas SLM	645 663
Lime firm	367	Black slate	665
Black slate	369	Gray shale sandy	674
Dark shale	376	Black shale	675
Lime	378	Sandy shale	685
Light sandy shale	386	Dark shale	703 Sand
Gray shale	396	Sand	710
Lime	399	Light shale sandy	721
Light shale	401	Gray shale	740
Gray shale	412	Light shale	753
Lime	415	Sand	758
Gray shale	423		
Black slate, gas & water	426		
Water sand - water	429		
Sandy lime	433		

Bottom 527 7' anchor on 4 7/8 csg.

858
141
+717