

4-11-25 ~~WE~~
 Plotted
 by

Company

Sec. 4 T. 11 R. 25
 Loc.

Farm Evans

No. 1

Total Depth 820

County Wyandotte


Comm. 6-9-32

Comp. 6-27-32

Shot or Treated

Contractor C. E. Wyett

Issued



Casing

20 in.	10 in.
15 1-2	8 1-4 60'
12 1-2	6 5-8 400'
13 3-8	5 3-16

Elevation

Production

4 7/8 525'

Figures Indicate Bottom of Formation

Soil	5'	Dark shale	378	gas bubbles	
Clay	30	Lime	380		
S - water	53	Sand	386	extra dark	
Green shale	55	Lime	391		
Gray shale	61	Gray shale	408		
Lime	62	Lime	411		
Gray shale	66	Black slate	413		
Lime	68	Gray shale	428	sandy	
Gray shale	75	Dark shale	430		
Lime hard	85	Lime	434		
Gray shale	88	Gray shale	437		
Lime & flint	104	Black slate	440	gas showing	
Black slate	105	Lime	442		
Gray shale	110	Black slate	450	sandy, coal & water	
Lime BF	132	Gray shale	468		
Dark shale	135	Black slate	470		
Lime	137	Sand	497	lots of water	
Gray shale	140	Gray shale	511		
L	148	Sandy lime	520	Brown lime	700
Light shale	220	Gray shale sandy	530	Dark sandy shale	765
Sandy shale gray	270	Dark shale	535	Sand	770
Red bed	272	Gray shale	558	Shale sandy lime	780
Light shale-muddy	275	Lime	559	and	790
S lime	285	Gray shale	562	Dark shale	805
Light shale	290	Dark shale	566	Sand	820
Gray shale sandy	300	Lime	567		
Blue shale	307	Dark shale	570		
Sandy shale gray	312	Light shale	575		
Dark shale-muddy	314	Gray shale	590		
Gray shale	317	Dark shale	595		
Lime	323	Gray shale	620		
Gray shale	327	Dark shale	630		
Sand-oil show	335	Gray shale	637		
Gray shale	347	Gas sand	653		
Lime	353	Black slate	655		
Gray shale	360	Gray Sandy shale	680		
Dark shale	371	Black slate	681		
Lime firm	374	Dark shale	696		