

Company

Sec. 17 T. 11S R. 25E
 Loc. S^W Cor.

Farm Ismert-Hincke

No.

Total Depth 733'

County Wyandotte


Comm. 4-27-31

Comp.

Shot or Treated

Contractor

Issued



Casing

20 in.	10 in.	
15 1-2	8 1-4	
12 1-2	6 5-8	180'
13 3-8	5 3-16	

Elevation 757

759
L & S

Production

Figures Indicate Bottom of Formation

Sand water	74	Lime	533
Lime	81	Dark shale	547
Lt sandy shale	174	Sand	550
Red shale	178	Sandy shale	560
Lime	185	Dark shale	575
Sandy lime	210	Brown & dark shale	590
Gray sandy shale	222	Sand - Bartlesville	599
Lt. sandy shale	227	Gray shale	608
Lime	233	Brown lime-	607
Blue shale	240	Dark gray shale	624
Gray shale	249	Lime	626
Lime	252	Brown shale	635
Gray shale	268	Dark gray shale	639
Lime	273	Sand	641
Black shale	276	Hard gray shale	646
59,000 cu.ft. gas		Sand- 2nd Bartlesville-	653
Oil sand (Peru)	288	Black shale	660
Gray shale	295	Sandy gray shale	680
Green shale	304	Dark shale	695
Lime	305	Sandy gray shale	710
Gray shale	315	Sand-little gas	712
Lime	321	Water sand	725
Gray shale	326	Miss Lime	733
Black shale	331		
Light sandy shale	340		
Sand	370	Bottom gas	276
Water sand	430	Plugged	277
Brown lime	435	Bridged	305
Dark shale	438		
Brown lime	449		
Shale	465		
Black shale	467		
Light sandy shale	484		
Lime	490		
Gray shale	500		
Black slate	503		
Dark shale	518		
Lime hard	522		
Light shale	530		

Comm. Apr. 27, 1931

Ismert Hinche
 177 and 180 W. Main

Company _____
 Farm _____
 Sec. 17 Tp. 11S R. 25E
 Map No. _____ Well No. _____

74 Sand water 74
 7 Lime 81
 93 Light sandy shale 174
 4 Red shale 178
 71 — 185
 25 Sandy lime 210
 12 Grey sandy shale 222
 5 Lt. — 227
 6 L — 233
 2 Blue shale 240
 7 Grey shale 249
 3 L — 252
 16 Grey shale 267
 1 — 273
 3 Black shale 276
 12 Oil sand 277
 7 Grey shale 295
 9 Green shale 304
 1 — 305
 10 Grey shale 315
 6 L — 321
 5 Grey shale 326
 5 Black shale 331
 5 Grey sandy shale 340
 30' Sand 376
 450 water sand 430
 1 Brown lime 435
 3 Dark shale 438
 11 Brown lime 449
 10 Shale 455
 2 Black shale 467
 17 Light sandy shale 484
 6 L — 490
 10 Grey shale 500
 3 Black shale 503
 15 Dark shale 518
 4 L — 522
 7 Light shale 530
 1 — 537

14 Dark shale 547
 3 Sand 550
 10 Sand, shale 560
 15 Dark shale 575
 15 Brown & dark shale 570
 9 Sand 597
 9 Grey shale 608
 1 Brown lime 609
 16 Dark grey shale 624
 2 L — 626
 9 Brown shale 635
 4 Dark grey shale 639
 12 Sand 641

57000 wpt gas
 Penn

5 Dark grey shale 646
 7 Sand 653 2nd Bud.
 7 Black shale 660
 20 Sandy grey shale 670
 15 Dark shale 695
 11 Sandy grey shale 710
 2 Sand 712
 13 water sand 725
 8 Mural — 733

Set 170 ft. 67% feet
 Bothing gas 276
 Plugged 777
 Bridged 305

From
 Jay Bradford
 Kansas City, Mo.

