

Plot 32-V-256

Company HENDERSON Et AL

Sec. 32 T. 11 R. 25 E

Farm Sanders

No. 3

Loc. Back of house on hill

County Wyandotte

Total Depth 200'

Comm. 1/8/47

Comp. 1/22/47



Shot or Treated

Contractor Hendee and Son

Issued

Casing

20 in.	10 in.
15 1/2	8 1/4
12 1/2	6 5/8
13 3/8	5 3/16



Elevation

Production

Figures Indicate Bottom of Formation

Shale and shelf lime	30
Shale grey	48
Lime	55
Shale grey	60
Lime (little water at 60')	69
Shale blue	88
Lime	91
Shale	94
Lime	97
Shale	99
Lime	112
Shale grey	116
Lime	129
Shale	131
Black slate	133
Shale dark	135
Lime	157
Black slate (water)	159
Shale	160
Lime	163
Shale	166
Lime	174
Shale grey	176
Shale red	181
Sand shaley, oil show	194
Shale grey	200
	T.D.