


EVERLY PENDERGRASS.
Twadell No. 1.

SEC. 4 T. 27 R. 11E.
SW SE NE

Total Depth. 1838
Comm. 3-27-35 Comp. 7-7-35
Shot or Treated.
Contractor.
Issued. 10-5-35

County. Greenwood.



CASING.

10" 551'
8" 860' UR 1060
6" 1410'

Elevation.

Production. DRY.

Figures Indicate Bottom of Formations.

yellow clay	28	
lime	40	
shale	50	
lime	55	
shale	60	
lime	64	
shale	68	
red rock	115	
shale	130	
lime	135	
shale	148	
lime	155	
shale	160	
lime	163	
shale	167	
lime	170	
shale	200	
lime	203	
shale	210	
lime	215	
shale	225	
shale sdy	235	
shale	268	
sand water	280	3BW
shale	290	
lime	300	
shale	325	
lime	350	
shale	365	
shale	375	
red rock	390	
lime	409	
shale	420	
red rock	430	
shale	440	
sdv shale	455	
shale	460	
sdv shale	470	
sand	475	3 BW
shale	535	
sdv shale	540	
shale	551	
shale	575	
shale	610	
lime	615	
shale	635	
lime	645	
shale	717	
lime	795	
lime	810	2 BW
lime	852	

shale	1015
lime	1020
shale	1025
sdv lime	1035 HFW
lime	1050
shale	1070
lime	1155 2 BW
shale	1160
lime	1209
shale	1223
lime	1235
shale	1270
lime	1295
shale	1350
lime	1359
shale	1365
lime	1370
shale	1387
lime	1400
shale	1460
lime shells	1490
shale	1500
shale sdy	1510
lime	1522
shale	1536
lime sdy	1540
shale	1555
sdv shale	1600
shale	1829
chat Miss.	1836
lime	1838
Total Depth.	
show oil 1836-38	est $\frac{1}{2}$ B.