

11-26-18W

DRILLERS LOG

No. 1 Newsom

CASING RECORD:

8-5/8" @ 303'
w/225 sx cement

5-1/2" @ 4578'
w/ sx cement

TOTAL DEPTH: 4580'

COMPANY: Patton Oil Company

CONTRACTOR: Red Tiger Drilling Company

COMMENCED: June 10, 1973

COMPLETED: June 27, 1973

DESCRIPTION:

SE
11-26S-18W
Edwards County,
Kansas

ELEVATION: 2161 Gr.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand	0	215	
Blue Shale	215	304	
Shale	304	460	
Sand	460	480	
Shale	480	500	
Redbed	500	590	
Anhydrite	590	595	
Redbed & Shale	595	1015	
Redbed	1015	1177	
Anhydrite	1177	1195	
Shale & Shells	1195	1420	
Shale & Lime Shells	1420	1845	
Shale & Lime	1845	2635	
Lime	2635	2725	
Lime & Shale	2725	3045	
Lime	3045	3130	
Lime & Shale	3130	3215	
Lime, Shale & Sand	3215	3250	
Lime & Shale	3250	3285	
Shale & Sand Tarkio	3285	3310	
Lime & Shale	3310	3483	
Lime	3483	3510	
Lime & Shale	3510	3545	
Lime	3545	3735	
Lime & Shale	3735	3770	
Lime	3770	3872	
Shale Heebner	3872	3878	
Lime Toronto & Douglas	3878	3930	
Shale & Lime	3930	4005	
Lime	4005	4545	
Shale, Sand & Lime	4545	4555	
Kinderhook	4555	4580	

RECEIVED
STATE CORPORATION COMMISSION
MAY 6 - 1974
CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
STATE GEOLOGICAL
SURVEY OF
KANSAS
JUN 1974

I certify that this is a true and correct copy of the above log to the best of my knowledge.