

COMPANY: Mull Drilling Co., Inc.
 CONTRACTOR: MALLARD DRILLING CO., INC.
 405 CENTURY PLAZA BLDG.
 WICHITA, KANSAS 67202

WELL NAME: #1 Slentz
 DESCRIPTION:
 NE NE NE 7-26S-18W

RIG NO.: 1
 TOTAL DEPTH: 4790'
 COMMENCED: August 24, 1984

COUNTY: Edwards
 ELEVATION:
 COMPLETED: September 2, 1984

CASING RECORD:

Surface: 10 jts. new 8 5/8" surface casing
 Production: none

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Soil, shale	0	498	Ran 10 jts. new 8 5/8" casing set @ 430' w/ 1d. joint. Cement w/ 300 sx. common, 3% cacl, 2% gel. Plug down @ 5:00 a.m. August 25, 1984. Cement did circulate, Haliburton-Pratt.
Sand	498	683	
Shale	683	1264	
Anhydrite	1264	1315	
Shale and lime	1315	3889	
Lime	3889	4593	Ran 4 Drill Stem Tests-Rickets Testers
Mississippi	4593	4790	

Ran 1 log-Petro Log

Plug hole w/ 130 sx. 60/40 pozmix 3% cacl, 2% gel as follows:
 1st plug @ 1260' w/ 50 sx.
 2nd plug @ 480' w/ 50 sx.
 3rd plug @ 40' solid bridge w/ hulls and rubber plug w/ 10 sx to top. 10 sx rathole, 10 sx mousehole.
 Plug down @ 11:45 p.m. September 2, 1984. Allied-Great Bend.

JAN 21 1986
 State Geological Survey
 WICHITA BRANCH

RECEIVED
 STATE CORPORATION COMMISSION

SEP 24 1984

CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) SS.
 COUNTY OF SEDGWICK)

I, JOHN JAY DARRAH, JR. of MALLARD DRILLING CO., INC., certify

that this a true and correct copy of the log of the #1 Slentz

well to the best of my knowledge