

11-26-18W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- GRAMEHART-MILLER OIL CO.
Farm- Newsom "B" No. 1

SEC. 11 T. 26 R. 18W
CS/2 NE SE

Total Depth. 4824
Comm. 10-14-54 Comp. 10-29-54
Shot or Treated.
Contractor. Graham-Messman-Rinehart Drlg Co.
Issued. 12-11-54

County Edwards
KANSAS



Elevation. 2165 K.B.

Production. Dry

CASING:
8 5/8" 291' cem w/250 sx.
5 1/2" 4660' cem w/ 75 sx.

Figures indicate Bottom of Formations.

sand	102
sand, clay	225
shale gray	310
shale sandy	535
red bed, shale	1939
lime, shale	4154
lime	4201
lime, shale	4281
lime	4422
lime, shale	4525
lime	4532
Coring	4547
lime, shale	4565
lime	4600
lime, shale	4614
lime	4658
lime, shale	4679
lime, sand	4742
lime, shale	4780
lime, arbuckle	4824 RTD.
Total Depth	

Tops:	
Heebner	3871
Brown Lime	3998
Lansing	4007
Kinderhook Sand	4528
Viola Chert	4569
Viola Dolomit e	4617
Simpson	4710
Arbuckle	4801