

STANOLIND OIL & GAS CO.  
J.D. Donovan No. 1.

Sec. 14 T. 26 R. 18W  
CSE SE  
660' N SL 1980' E WL

Total Depth, 4984'  
Comm. 4-19-36 Comp. 2-12-37  
Shot or Treated.  
Contractor.  
Issued. 4-3-37

County. Edwards



CASING:  
16" 211'  
8 5/8" 4038'3"  
7" 4480'  
5 3/16" 4578'

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

surface	10	lime	4160	shale green	4540
sand, gravel & shells	134	shale	4170	lime	4555
sand, shells & shale	258	lime	4221	shale green & lime	4568
shale & shells	427	shale	4226	lime	4577
sand & shale	490	lime	4247	brkn lime	4586
red bed, sand & shells	573	sand	4259	brkn sand	4590
lime & anhydrite	600	lime	4306	SLCorr. 4590-4578	
red bed, shale & shells	830	shale	4313	sand	4630
shale & shells	1168	brkn lime & shale	4320	shale	4632
anhydrite & lime	1195	lime	4371	brkn lime	4645
shale, shells & salt	1340	brkn lime & shale	4385	brown sand	4655
shale & lime	1900	shale	4390	lime grey	4665
brkn lime	2010	shale & lime shells	4404	sand	4670
brkn lime & shale	2150	shale	4406	lime	4679
shale & lime shells	2180	lime	4413	sand	4717
lime & shale	2253	shale	4417	lime	4749
lime	2330	lime	4420	sand	4753
lime & shale	2414	shale	4425	lime	4795
brkn lime	2512	lime	4428	shale	4800
lime & shale	2559	shale	4436	lime	4804
brkn lime	2578	lime	4445	sand	4808
shale	2588	shale	4456	lime	4854
brkn lime	2656	shale & lime shells	4463	shale	4861
brkn lime & shale	2715	lime	4468	shale black	4880
brkn lime	2797	brkn lime	4483	lime & shale	4884
shale & lime	2924	lime	4505	lime	4977
brkn lime	2938	shale	4517	slate black	4980
shale & lime	2974	lime & shale	4532	lime	4984
shale	2991	lime	4545	Total Depth.	
lime & shale	3062	sand	4547		
brkn lime	3121	chert & red rock	4566	Top Lansing Lime	4028
shale & shells	3145	sand	4569	Top Viola Lime	4642
brkn lime & shale	3282	lime	4576	Top Simpson Sand	4790
brkn lime	3300	sand	4580	Top Siliceous	4872
coarse gravel	3335	At this depth the tools were lost.			
shale & lime shells	3418	Hole cemented back at 4392.			
shale	3426	Rotary tools moved in.			
shale & lime shells	3548	Cemented back to 4118.			
brkn lime & shale	3685	cement	4118-4215		
lime	3850	lime	4225		
brkn lime & shale	3877	shale	4235		
brkn lime	3880	lime	4245		
lime	3900	cement	4280		
lime (cored)	3920	lime	4302		
lime	3939	bottom of cement 4302			
shale	3960	lime & shale	4312		
shale & lime	4007	lime	4320		
shale	4015	lime & shale	4332		
shale black (cored)	4028	SLCorr. 4332-4350			
lime (cored)	4032	lime	4354		
limey shale (cored)	4035	shale	4357		
Top Lansing 4028		lime	4420		
grey green limey shale (cored)	4036 1/2	lime & shale	4440		
lime (cored)	4054	lime	4454		
lime grey	4085	shale & lime	4474		
hole filled up 200'		lime	4486		
in 2 hrs with wtr fr m		shale	4490		
4070-77		lime	4512		
brkn lime	4100	shale & lime	4515		