

17-26-18W


KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY SKELLY OIL
 FARM Belcher "A" NO. 1

SEC. 17 T. 26 R. 18W
 LOC. C SE NW
 1991' FWL 1995' FNL NW/4

TOTAL DEPTH 3422' Schl TD 3423'
 COMM. 1-25-65 COMP. 2-2-65
 SHOT OR TREATED
 CONTRACTOR WESTERN PETROLEUM
 ISSUED 8-20-66

COUNTY Edwards



CASING
 20 10
 15 8 5/8" 325' cem w/ 200 sx
 12 6
 13 5

ELEVATION 2189' KB

PRODUCTION DRY (Tark)

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand & clay	40
sand & gravel	160
shale & sand	250
shale	325
shale	550
red bed	965
shale	1248
anhydrite	1266
shale	2080
shale & lime	3360
lime & shale	3422
No log	3423
Total Depth	

Tops: SCOUT	
Base Blaine	672
Anhydrite	1252
Chase	2446
Ft Riley	2636
Council Grove	2826
Wabaunsee	3268
Wabaunsee sand	3328
Tarkio	3401

DST # 1 3318-3360' tool open
 45 min., weak blow, died in 20 min.
 rec. 40' drilling mud, IFP-9# 45 min,
 FFP 18#; IBHP-1005# 45 min; FBHP 850#.