

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


19-26-18W

Company- AYLWARD DRLG. CO., KENNETH RUPP ET AL
Farm- Belcher No. 1

SEC. 19 T. 26 R. 18W
C SW NE

Total Depth. 4726'
Comm. 8-22-63 Comp. 9-9-63
Shot or Treated.
Contractor. Aylward Drilling Co.
Issued. 4-11-64

County Edwards
KANSAS



CASING:

8 5/8" 209' cem w/200 sx.
5 1/2" 4723' cem w/300 sx.

Elevation. 2197' DF

Production. 590 MCFG

Figures Indicate Bottom of Formations.

sand	100
shale & shale	700
shale	2320
shale & lime	2475
lime & shale	3090
lime	3155
lime & shale	3331
lime	3346
sand	3375
lime & shale	4190
lime	4726 RTD
Total Depth	

TOPS: LOG

Chase Group	2465
Council Grove Group	2640
Wabaunsee Group	3259
Pillsbury (Langdon) Shale	3315
Tarkio Sandstone	3336
Topeka	3594
Heebner	3988
Lansing-Kansas City	4126
Base Kansas City	4509
Marmaton	4532
Mississippi	4686

DST 3312-46' Op 1 hr. 40", GTS/2", Gauge
1,020 MCF/5", 1450 MCF/10", 2310 MCF/20",
2500 MCF/30", 3000 MCF/50", 3120 MCF/70",
3200 MCF/90", 3200 MCF/100" Sprayed fine
mist of wtr. Rec. 70' SW, IBHP 1155#/30",
FBHP 1117#/60", Fp 139#-391#.

DST 4682-4701' Op 1 hr. 40", GTS/5", Gauge
244,000/10", 174,000/30", 122,000/40", Rec.
30" GCM, IBHP 1534/30", FBHP 1449#/60",
FP 75#-38#.

DST 4701-26' Op 1 hr. Rec. 30' mud, IBHP
177#/30", FBHP 275#/30" FP 56#-60#.