

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


24-26-18W

Company- WESTERN PETROLEUM
Farm- Donovan No. 1

SEC. 24 T. 26 R. 18W
CSW NW

Total Depth. 4795
Comm. 11-20-64 Comp. 12-10-64
Shot or Treated.
Contractor. CO. Tools
Issued. 4-10-65

County Edwards
KANSAS



CASING:

8 5/8" 335' 300sx.

Elevation. 2173' KB

Production. Dry

Figures Indicate Bottom of Formations.

sand	120
shale	500
redbed & Gypsum	1162
Anhydrite	1172
Anhydrite, redbed & shale	1672
shale, lime, & shells	2060
shale & lime	2280
lime & shale	3700
lime	3803
lime & shale	4025
lime	4081
lime & shale	4100
lime	4252
lime & shale	4325
lime	4390
lime & shale	4520
lime	4544
lime & sand	4560
chert & sand	4570
sand & lime	4613
chert & lime	4644
chert	4656
chert, sand & lime	4707
lime, shale & sand	4730
lime & shale	4795
RTD	4795

TOPS: LOG

Anhydrite	1164
FT. Riley	2490
Tarkio	3300
Heebner	3892
Lansing	4033
Base Kansas City	4388
Cherokee	4504
Mississippi	Absent
Kinderhook	4539
Viola	4610

Simpson 4720
LTD 4780

WST #1 3206-3265 (Wabaunsee).
Tool opn. 47min., weak blow 12 min., Rec
8' Drlg. mud. IBHP 915# 30min.; FBHP 145#
30 min.; IFP 0#; FFPO#; IHMP 1785#