


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bk Bldg., Wichita, Kansas.

THE FRANKLIN DRG. CO., INC.
Rossillion No. 5.

SEC. 1 T. 23 R. 14E
C EL SE SE

Total Depth. 1547'
Comm. 9-14-36 Comp. 10-15-36
Shot or Treated.
Contractor.
Issued. 11-7-36

County. Coffey



CASING:
10" 70'
8" 1127'
6 5/8" 1512'

Elevation.

Production. Pot. 68 B.

Figures Indicate Bottom of Formations.

soil	5	shale	1310
clay	18	shale dark	1350
gravel	25	shale caving	1506
lime	35	Mississippi lime	1539
shale	40	sand sh oil	1541
lime	45	sand hrd some wtr	1542
shale dark	50	brown oil sand	
red rock	55	fine free oil	1546
lime	68	brown oil sand	
shale	72	mixed with	
lime	80	white lime	1547
shale	100	Total Depth.	
lime	105		
shale	215		
lime	220		
shale dark	225		
lime	230		
shale	380		
lime	400		
shale	405		
lime	420		
shale dark	425		
lime	490		
shale	545		
lime	585		
shelly lime	605		
water sand water	615		
sholly lime	640		
lime	655		
shale	660		
red rock	670		
shale	695		
lime hrd	805		
lots of water	730'		
shale	810		
lime	830		
shale	975		
lime	980		
shale	985		
lime caving	990		
lime	1005		
shale caving	1060		
lime	1075		
shale	1090		
lime	1105		
shale	1147		
oil sand	1158		
shale light	1195		
lime	1197		
shale dark	1200		
sand	1223		
shale dark	1240		
sand water	1255		