

WICHITA BRANCH

IMPORTANT

Kans. Geo. Survey request samples on this well.

KANSAS DRILLERS LOG

S. 29 T. 26 R. 18 W

API No. 15 — 047 — 20,534
County Number

Loc. NW SW SE

County Edwards

Operator
Alpine Drilling Co., Inc.

Address
800 Bitting Bldg. Wichita, Kansas 67202


Well No. #1 Lease Name Gamble

Footage Location
990 feet from (N) (S) line 1650 feet from (E) (W) line

Principal Contractor Husky Drilling Co., Inc Geologist Jon T. Williams, Jr.

Spud Date August 3, 1979 Total Depth 4840 P.B.T.D.

Date Completed August 11, 1979 Oil Purchaser



Locate well correctly
Elev.: Gr. 2188
DF 2190 KB 2193

CASING RECORD

Report of all strings set— surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4	8-5/8	28	310	common	275	2%gel, 3%cc

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS	Oil bbls.	Gas MCF	Water bbls.	Gas-oil ratio	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator ALPINE DRILLING CO., INC.

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.: dry hole

Well No.

1

Lease Name

Gamble

s 29 T 26 S R 18 W E
W

WELL LOG


Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
			<u>LOG TOPS</u>	
			Heebner	4010 -1817
			Toronto	4034 -1841
			Douglas	4052 -1859
			Brown Lime	4156 -1963
			Lansing	4166 -1973
			B/Kansas City	4503 -2310
			Cherokee Shale	4672 -2479
			Miss	4732 -2539
			Viola	4773 -2580
			Simpson Shale	4809 -2616
			LTD	4840 -2647
			RTD	4841 -2648

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received


 Jon T. Williams, Signature Jr., President

Title

August 13, 1979

Date



29-26-18W

800 Biting Bldg
Wichita, Kansas 67202
Phone 316 - 263-7904
Mobile Phone 316 - 793-7859 Unit 7070

August 13, 1979

WELL LOG-----Gamble No. 1
Located: NW SW SE of Sec. 29-26S-18W, Edwards Co., Kansas

OWNER: Alpine Drilling Co., Inc.
ROTARY CONTRACTOR: Husky Drilling Co., Inc.

COMMENCED: August 3, 1979
COMPLETED: August 10, 1979

Rotary Total Depth: 4840'

LOG

CASING RECORD

0 - 41 Surface soil & sand
 41 - 180 Sand
 180 - 310 Sand & clay
 310 - 525 Shale
 525 - 891 Shale & sand
 891 - 1246 Red Bed & shale
 1246 - 1275 Anhydrite
 1275 - 2114 Shale & shells
 2114 - 4187 Shale & lime
 4187 - 4485 Lime
 4485 - 4706 Lime & shale
 4706 - 4800 Lime & chert
 4800 - 4840 Lime & shale

Spud surface hole @ 2:55 p.m. - 8-3-79
cut 310' - set at 306' w/275 sx by
Allied.

Plugged @ 1 a.m. 8-11-79 by Allied.