

D R I L L E R S L O G

BEELEER #1

EDWARDS, KANSAS

C SE SW

Sec. 36-26S-18W

36-26-18W

Company: BEREN CORPORATION

Contractor: BEREDCO INC.

Comm: 11/30/80

Comp.: 12/14/80

State Geological Survey
WICHITA, BRANCH
DUPLICATE

Casing: 8 5/8", 28# set at 507' with 350 sacks 60-40 poz, 2% gel, 3% CC
4 1/2", 10 1/2# set at 4844' with 200 sacks 60-40 poz, 2% gel, 10% salt,
10# per sack Gilsonite .75% CPR-L

FORMATION	FROM	TO
Sand	0'	137'
Red Bed	137'	510'
Cemt.	510'	525'
Red Bed & Shale	525'	602'
Red Bed	602'	1210'
Red Bed & Sime Stringers	1210'	1710'
Shale	1710'	2198'
Lime & Shale	2198'	4170'
Kansas City	4170'	4170'
Lime & Chert	4170'	4290'
Kansas City	4290'	4290'
Lime	4290'	4423'
Lime & Shale	4423'	4669'
Mississippi	4669'	4740'
Lime Shale & Chert	4740'	4853'
Chert	4853'	4855'
STATE OF KANSAS		Rotary Total Depth - 4855'

SS:

COUNTY OF SEDGWICK

I certify that this is a true and correct copy of the above log as shown by the drilling reports.

BEREDCO

Jerome D. Marcus

STATE RECEIVED
JAN 7 1981
CONSERVATION DIVISION
Wichita, Kansas

Subscribed and sworn to before me this 29th day of December, 1980.



Marca J. Dearth