

5-26-20W
✓


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- IMPERIAL OIL CO.
Farm- Froetschner No. 1

SEC. 5 T. 26 R. 20W
C NE SE

Total Depth. 4791'
Comm. 12-7-61 Comp. 12-19-61
Shot or Treated.
Contractor. Imperial Oil
Issued. 3-17-62

County Edwards
KANSAS



CASING:
8 5/8" 202' cem w/175 sx.

Elevation. 2236' KB

Production. Dry

Figures Indicate Bottom of Formations.

sand	202
shale & sand	710
Anhydrite	735
shale & shells	2215
shale & lime	2465
lime & shale	4075
lime	4718
chert & lime	4791 RTD
Total Depth	

TOPS:

Heebner	3979
Brown Lime	4089
Lansing	4100
Base Kansas City	4485
Cherokee Shale	4624
Pennsylvanian Conglomerate	4690
Mississippi (Osg)	4712

DST #1 4687-4718', op 1 hr & 25 mins.
Rec. 400' muddy water. IBHP 1500#,
IFP 0#, FFP 170#, BHP 1100#.