

Operator: Texas Oil & Gas Corp. DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No. 1 Lease Name Einsel "C" Shut-in Gas Well

S 31 T 26S R 20 W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Herrington	2494	-215		
Cottonwood	3020	-741		
Topeka	3645	-1366		
Heebner	4047	-1768		
Lansing	4169	-1890		
Swope	4522	-2243		
Hertha	4562	-2283		
Mississippi	4814	-2535		
TD	4940	-2661		
PBTD	4884	-2605		
DST #1, 4821-40', (Mississippi) w/results as follows: Mis-run (tool plugging).				
DST #2, 4822-40', (Mississippi) w/results as follows: IFP/30": tool plugging, strong blow; ISIP/60": 1504#; FFP/45": 94-104#, strong blow; FSIP/90": 1514#; Rec 70' DM.				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Harold A. Brown
 HAROLD A. BROWN Signature
 District Geologist Title
 May 12, 1978 Date