

KANSAS

State Geological Survey
WICHITA BRANCH

WELL COMPLETION REPORT AND
DRILLER'S LOG

S. 7 T. 26 R. 31 E

API No. 15 — Finney — 15-055-20-440
County Number

Loc. G NW/4


Operator
Continental Energy

County Finney

Address
South Star Route, Garden City, KS 67846

640 Acres
N

Well No. 1-R Lease Name Kisner



Footage Location
1320 feet from (N) (S) line 1320 feet from (E) (W) line

Locate well correctly

Principal Contractor Takin Drilling Geologist Ron Osterbuhr

Elev.: Gr. 2841

Spud Date 12-30-80 Date Completed 1-3-81 Total Depth 2708 P.B.T.D.

Directional Deviation None Oil and/or Gas Purchaser Northern Natural

DF. KB

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	24#	573'	H Lite 3%	150 225	3% G. G. Ca. Cl. 1/4 flocele
Production	7 7/8"	4 1/2"	10 1/2#	2708'	Lite 3% 50/50 Poz	350 150	G. G. 1/4 flocele 6% gel 18% salt

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	SSB II	2669-2677
			2	SSB II	2644-2650

TUBING RECORD

Size	Setting depth	Packer set at
2 1/16"	2705	None

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
20,000 gal 3% gelled acid w/14,000 lbs. 20-40 frac sand	2669-2677 2644-2650

INITIAL PRODUCTION

Date of first production 1/20/81	Producing method (flowing, pumping, gas lift, etc.) swab
RATE OF PRODUCTION PER 24 HOURS	Oil 0 bbls. Gas 20,000 MCF Water 25 bbls. Gas-oil ratio 0 CFPB
Disposition of gas (vented, used on lease or sold) Vented	Producing interval(s) 2669-2677 2644-2650

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

Continental Energy

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Gas

Well No.

1-R

Lease Name

Kisner

S 7 T 26 R 31 E W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Clay & Sand	450			
Shale	574			
Clay Sh & Sd	1246			
Sand & Shale	1746			
Shale	1977			
Shale-Salt & Anhy	2513			
Anhy & Lime	2708			

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Paul Means

Signature

Owner

Title

Date