


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- SOUTHWESTERN EXPLORATION CO.
Farm- Kleysteuber No. 1

SEC. 30 T. 26 R. 31W
CNW

Total Depth. 2699
Comm. 1-9-55 Comp. 1-14-55
Shot or Treated.
Contractor. Rocket Drlg.
Issued. 4-9-55

County Finney
KANSAS



Elevation. 2834 R.B.

Production. 11,400,000 gas

Figures indicate Bottom of Formations.

shells & sand	250
sand	390
shale	460
shale & shells	1390
shale, shells & xyn	
strks	1890
shale & shells	2250
shale & lime	2545
brkn lime	2630
lime & shale	2699
Total Depth	

Tops:	
Herington	2605
Upper Krider	2615
Lower Krider	2652
Winfield	2693

RTD 2694

Cable Tool Completion:

2-19-55 Drilled plug & D.D. to 2699--show
of gas natural (100 MCF) Perf 20 ϕ 2670-73,
squeezed w/175 sx. cem. Packer @ 2659.
Dolofrac w/2000 gals., open flow 850,000
CFG + large amount of water.

Shut in, SIP 400#, open flow 20 mins.,
guaged 1,250,000 CFG + 17 BWP

Shut in, SIP 400#, open flow 20 mins, guaged
950,000 CFG + 8 BWP.

Halliburton retainer @ 2666

Squeezed w/200 sx. cem. Cleaned out to
2667. Perf. 72 ϕ 2652-64--good show gas.
Perf. 108 ϕ 2622-40--est. 150,000 CFG
Halliburton packer @ 2644. Fracked w/6000
gal.
3-8-55 On 72/20 tested 11,400,000 CFG, SIP
410#. CTID 2699