


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- KANSAS-NEBRASKA NATURAL GAS CO. & SKELLY
Farm- J. Lightner **No. 1** OIL CO.

SEC. 1 T. 26 R. 32W
NE SE SE NW
200' fr EL, 360' fr SL

Total Depth. 2700' **PB 2663'**
Comm. 2-23-54 **Comp.** 2-27-54
Shot or Treated.
Contractor. Honaker Drlg. Co. & C. L. Hinds
Issued. 12-18-54

County Finney
KANSAS



Elevation. 2812'

Production. 1,473,000 cu. ft. G.

Figures indicate Bottom of Formations.

| | |
|-----------------|-------|
| sand | 50 |
| sand and gravel | 360 |
| sandy clay | 375 |
| blue shale | 558 |
| blue shale | 900 |
| red bed & shale | 1200 |
| gyp and shale | 1270 |
| salt and shale | 1540 |
| shale | 1900 |
| gyp and shale | 2430 |
| lime and shale | 2690 |
| lime | 2700 |
| Total Depth | |
| Plug Back | 2669' |

Tops:
Winfield Lime 2681

Ran Halliburton electric log.

Shot or Acid Treatment Record:
 3-15-54, 1000 gals. shot between 2680-2700'
 3-19-54, 4000 gals. shot between 2618-2654'
 Dolo-frac.

Producing Formation Hugoton Gas Pay top 2618'
 bottom 2654'

Significant geological formations Winfield
 lime gas from 2618 to 2654'