


Ransom  
 Greenwood County -  
 Smith & Waidner  
 Jones Farm #1  
 21-23-13

No. \_\_\_\_\_

Company \_\_\_\_\_

Elev. \_\_\_\_\_ T. D. \_\_\_\_\_

Log No. \_\_\_\_\_



Soil - 5  
 R.R. - 35  
 sl - 60  
 L - 80  
 sl - 100  
 L - 110  
 sl - 160  
 L - 170  
 sl - 200  
 L - 210  
 sl - 260  
 L - 270  
 sl - 310  
 L - 320  
 sl - 365  
 sdpt - 385  
 sl - 420  
 sh - 445  
 sl - 475  
 s - 505  
 sl - 620  
 s - 637  
 L - 660  
 sl - 665  
 L - 675  
 sl - 680  
 L - 725  
 sl - 740  
 L - 840 (Hi.F.M.)  
 s - 860  
 L - 885  
 sl - 905  
 RR - 915  
 sl - 950  
 L - 1010  
 sl - 1020 (2 B.W. at 1025)  
 L - 1065  
 sl - 1095  
 s - 1110  
 sl - 1205  
 L - 1215  
 sl - 1230  
 L - 1250  
 sl - 1275  
 L - 1285  
 sl - 1295

L - 1315  
 sl - 1322  
 L - 1332 (water)  
 sl - 1375  
 sl - 1425  
 L - 1435  
 sl - 1515  
 sh - 1525  
 sl - 1620  
 sh - 1734  
 L - 1737 (mistake)  
 s - 1766 (oil land) T.D.

# 2124



Soil	5	5	
Red rock	30	35	
Slate	25	60	
Lime	20	80	
Slate	20	100	
Lime	10	110	
Blue slate	50	160	
Lime	10	170	
Slate	30	200	
Lime	10	210	
Slate	50	260	
Lime	10	270	
Slate	40	310	
Lime	10	320	
Slate	45	365	
Sandy lime	20	385	
Slate	35	420	
Shale	25	445	
Slate	30	475	water
Sand	30	505	2 bailers 475 505
Slate	115	620	
Sand	17	637	Hole full
Lime	23	660	
Slate	5	665	
Lime	10	675	
Slate	5	680	2 bailers water 700
Lime	45	725	
Slate	15	740	
Lime	100	840	hole water
Sand	20	860	more water
Lime	25	885	
Slate	30	905	
Red rock	10	915	
Slate	35	950	
Lime	60	1010	
Slate	10	1020	1 bailer water 1025
Lime	45	1065	895
Slate	30	1095	
Sand	15	1110	
Slate	95	1205	
Lime	10	1215	
Slate	15	1230	
Lime	20	1250	
Slate	25	1275	
Lime	10	1285	
Slate	10	1295	
Lime	20	1315	
Slate	7	1322	
Lime	10	1332	Water 1332
White slate	38	1370	
Black slate	5	1375	
Shale	50	1425	
Lime	10	1435	
Slate	80	1515	
Shale	10	1525	
White slate	5	1530	
Black slate	90	1620	
Shale	114	1734	
Lime	3	1737	Miss lime
Oil sand	29	1766	
Total depth		1766	

Casing Record

12 1/2" Casing	637'
10 "	928
8 1/4 "	1334
6 5/8 "	1702

This was drilled to 1794' with break from 1776' to 1788' then good sand for next three or four feet. No water.

water  
2 bailers 475 505

Hole full

2 bailers water 700

hole water

more water

Water 1332

Miss lime