

4-26-33W

KANSAS WELL LOG BUREAU---KANSAS GEOLOGICAL SOCIETY
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY CITIES SERVICE OIL COMPANY


FARM Drussell "B", NO. 1

SEC. 4 T. 26 R. 33W
LOC. NE NE NE SW
100' S & W of cen.

TOTAL DEPTH 2730
COMM. 4-13-50 COMP. 4-18-50
SHOT OR TREATED
CONTRACTOR Barbour Drlg Co.
ISSUED 5-26-51

COUNTY Finney

KANSAS



CASING

8 5/8" 800' cem w/325 SX
5 1/2" 2729' cem w/900 SX

ELEVATION 2910

PRODUCTION I.P. 8,260,000 gas

FIGURES INDICATE BOTTOM OF FORMATIONS

sand, clay 0- 525
clay 800
shale 805
red bed, shale 1300
red bed, sand 1825
anhydrite, shale 1940
red bed, shale,
anhydrite 2165
shale, lime 2510
lime 2730
Total Depth

Tops:
Herington 2530
Upper Krider 2554
Lower Krider 2581
Winfield 2612
Upper Ft. Riley 2672

Perf:
110 Shots 2556-78
60 " 2586-98
30 " 2612-18
70 " 2624-38
60 " 2692-2704
20 " 2682-86

SIP 392.1