

6-26-33W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

Company - WHITE EAGLE OIL COMPANY  
Farm - A. Riggs No. 1

SEC. 6 T. 26 R. 33W  
CSE/4  
1320' NSL, 3960' EWL of Sec. 1

Total Depth. 2738  
Comm. 4-27-49 Comp. 6-2-49  
Shot or Treated.  
Contractor.  
Issued. 8-13-49

County. Finney  
KANSAS



Elevation. 2953 *and*

Production. 10,514,000 gas

CASING:

10 3/4" 568' cem w/350 sx.  
7" 2574' cem w/750 sx.

Figures Indicate Bottom of Formations.

sand, clay	200
sand rock, sand	400
sand cly	535
shale blue	575
shale	605
shale blue	855
red bed	1120
redbed, sand	1250
salt, shale	1300
shale, gyp	1340
redbed, shale	1750
redbed, sand	1875
redbed, anhydrite	2060
shale, anhydrite	2250
anhydrite	2330
lime, shale	2410
lime, anhydrite	2515
lime	2585
lime brkn	2591
lime	2627
shale	2640
lime brkn	2647
lime	2674
red rock	2695
lime	2738
Total Depth	

Tops: Crown level meas.

Herrington	2581-2600
Krider	2602-2624
Winfield	2639-2663
Upper Ft. Riley	2696-2738

Rotary total depth 2586'

Liner record: 5 1/2" 193'  
Acidized w/2000 gals 15% acid,  
Acidized w/6000 gals 7 1/2% acid  
Acidized w/10,000 gals. 15% acid.