

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas


17-26-33W

Company- NORTHERN NATURAL GAS COMPANY
Farm- Stone "A" No. 1

SEC. 17 T. 26 R. 33W
SE SE NW
200' N & 200' W of Cen. of Sec.

Total Depth. 2725' CTTD
Comm. 3-7-54 Comp. 3-28-54
Shot or Treated.
Contractor.
Issued. 5-25-57

County Finney KANSAS



Elevation. 2917'

Production. 2,918 MCF

CASING:

10 3/4" @438' w/325 sx cem.
7" @2536.8' w/700 sx cem.
5" Perf. Liner @2725'

Figures indicate Bottom of Formations.

sand & Limestone	125
sand & Gypsum	465
sand & clay	500
sand & Gypsum	525
Gypsum	575
blue shale	953
red bed, Anhydrite	2260
lime & shale	2373
Anhydrite, shale	2435
lime & shale	2541
lime & Dolomite	2545 RTD
Dolomite	2550
shale	2570
Dolomite	2612
shale	2628
Dolomite	2670
Brown shale	2690
Dolomite	2725 CTTD

Total Depth

TOPS

Herington	2535
Lower Krider	2567
Winfield	2628
Upper Fort Riley	2690

Shows of Oil, Gas, Water

SG	2588
SG	2605
SG	2614
.196 MCF	2620
.220 MCF	2625
.225 MCF	2640
.225 MCF	2667
.240 MCF	2708
.245 MCF	2725