

22-26-33W

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY CITIES SERVICE OIL CO.

SEC. 22 T. 26 R. 33W

FARM Warren

NO. 1

LOC. NE NE SW

100' S. & 100' W.
of Center

TOTAL DEPTH 2785

COMM. 5-15-50

COMP. 5-25-50


SHOT OR TREATED

CONTRACTOR Barbour Drlg. Co.

ISSUED 6-2-51

COUNTY Finney

KANSAS



CASING

8 5/8" 800' cem w/325 sxs.
5 1/2" 2784' cem. w/500 sxs.

ELEVATION 2933.

PRODUCTION 8,770,000 gas

FIGURES INDICATE BOTTOM OF FORMATIONS

sand & gravel	130
sand & clay	555
sand & shale	805
shale & red bed	1300
anhydrite	1420
shale & red bed	1930
anhydrite & shale	2145
shale & lime	2615
lime	2680
lime & shale	2740
lime	2785
Total depth	

Tops:

Herington	2584
Upper Krider	2625
Lower Krider	2641
Winfield	2663
Upper Ft. Riley	2719

Perforated:

60 shots	2616-32
42 shots	2642-56
18 shots	2674-80
36 shots	2686-98

SIP 413.7#