


SUPERIOR OIL CORP.
David Jones(West) No. 14.

SEC. 21 T. 23 R. 13E
NE SW NE SW
860' S NL 745' W EL SW $\frac{1}{4}$

Total Depth. 1742'
Comm. 7-24-37 Comp. 8-25-37
Shot or Treated. 2000 Gals. 15% acid.
Contractor. Co. Machine
Issued. 9-18-37

County. Greenwood



CASING:
12 $\frac{1}{2}$ " 421'4"
10 " 913'
8 " 1468'
6 5/8" 1720'
2" 1712'

Elevation.

Production. 96 Bbls.

Figures Indicate Bottom of Formations.

soil	14
red bed	38
shale blue	77
lime	81
shale	86
lime	105
shale	157
lime	162
shale	243
lime	251
shale	265
lime	279
shale	367
wtr sand	375
shale	436
lime	453
shale	485
lime	495
shale	620
lime	631
lime	667
shale	672
lime	848
sdv shale	850
lime	855
wtr sand HEW	878
lime	895
red bed	905
shale	928
brkn lime	939
lime	1065
shale	1200
lime	1208
shale	1237
lime	1251
shale	1295
lime	1300
shale	1323
lime	1327
gas sand	1328
lime wtr	1348
shale	1356
lime	1361
shale	1435
sand	1451
shale	1500
lime	1505
shale	1712

SIM 1712=1720

lime 1729
lime OIL 1742
Total Depth.

Prod. before treating 24 B., 2 BW.
Prod. after treating 96 B., 10 BW.