

COMPANY SUNRAY OIL CORPORATION

SEC. 21 T. 23 R. 13E

FARM Jones "E"

NO. 4

LOC. SE NW SE

990' SNL 1024' EWL SE $\frac{1}{4}$

TOTAL DEPTH 1716

COUNTY Greenwood

COMM. 12-8-50


COMP. 12-15-50

KANSAS

SHOT OR TREATED

CONTRACTOR Jackman & Jackman

ISSUED 4-7-51



CASING

8 5/8" 82'

5 1/2" 1701'

ELEVATION 1140 RB

PRODUCTION Pmp. 25 BOPD

FIGURES INDICATE BOTTOM OF FORMATIONS

lime & shale	115
shale	145
lime & shale	190
lime hrd	255
shale	270
lime, hrd & rough	285
shale & lime	400
lime shells & shale	470
shale	575
shale & shells	585
lime	640
shale brks	650
lime	880
shale	910
lime	960
lime hrd	1025
lime	1035
shale & shells	1330
shale	1692
lime, Miss.	1702
lime, pay	1716 RTD
Total Depth	

Tops:

Miss. Chat	1691
Miss. Dolomite	1709

DST: 1701-16 RTD, open 1 hr.  
 rec. 5' free oil, 60' heavy oil  
 cut mud; BHP #220 CO-1716 TD,  
 Swb. 1.9 BOPD; 3000 A; Test 70  
 BO plus no wtr. 14 hrs.