

32-26-33W


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company - MAGNOLIA PETROLEUM CO.
Farm - A.F. Atkins Unit No. 1

SEC. 32 T. 26 R. 33W
NW NW SE

Total Depth. 2804 K.B.
Comm. 10-14-49 Comp. 10-25-49
Shot or Treated. Acid
Contractor. Barnett Drlg.
Issued. 1-14-50

County. Finney
KANSAS



Elevation. 2937' *Ind.*

Production. 5,010,000 gas

CASING:

10 3/4" 868' cem w/500 sx.
6 5/8" 2800' cem w/1000 sx.

Figures Indicate Bottom of Formations.

sand	50
clay, sand	110
sand	280
sh lc blue	380
sand, shale	530
shale, shells	560
shale	675
lime sdy	745
shale blue pyrite	815
shale	820
sand red, shale	840
red be d	1170
redbed, shells	1470
sand, salt	1570
shale, shells	1660
red rock, shale	1820
anhydrite	1940
shale, shells	2040
red rock, shale	2070
shale, shells	2140
red rock, shale	2250
anhydrite, red rock	2330
lime	2390
anhydrite	2515
lime	2555
shale, lime	2600
lime	2804
Total depth K.B.	

Top:
Towanda 2719 KB

Ran Halliburton elec. log.
Perf. 2650-77 w/144 sh., acid w/7000 gals.
Perf. 2618-36 w/96 sh., " " " "
Both zones - acidized w/10000 gals.
Perf. 2592-2610 w/96 sh., acid w/7000 gals.
Perf. 2568-77 w/48 shl, acid w/ 17,000 gals.