

6-26-34W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company - WHITE EAGLE OIL COMPANY -
Farm - Carlton No. 1

SEC. 6 T. 26 R. 34W
SW SW NE
3443' NSL, 2640' EWL

Total Depth. 2718
Comm. 6-19-49 Comp. 8-19-49
Shot or Treated. Acid
Contractor.
Issued. 9-24-49

County. Finney
KANSAS



Elevation. 3018 Ind

Production. 22,879,000 gas

CASING:

10 3/4" 562' cem w/400 sx.
7" 2514' cem w/750 sx.

Figures Indicate Bottom of Formations.

sand, gravel	285
sand, clay	560
shale	570
shale blue, sand	830
shale blue	840
red bed	970
sand red, red rock	1215
red rock, anhydrite	1400
shells, shale, red rock	1790
anhydrite, red rock, shale	1950
shale, red rock	2125
shale, anhydrite	2250
lime, anhydrite	2405
lime, shale	2465
lime, shale, anhyd. RTD	2530
lime, shale, anhydrite	2530
lime	2590
lime brkn	2595
lime	2622
shale	2645
lime	2687
shale	2695
lime	2718
Total depth	

Tops:

Herrington	2535-2554
Krider	2558-2576
Winfield	2593-2621
Upper Ft. Riley	2649-2684
Lower Ft. Riley	2701-2714

Liner record:

5 1/2" 225' from 2493-2718'.
Acidized with 13,000 gals acid 15%
and 4,000 gals 7 1/2% acid.