

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

Company- CHAMPLIN OIL & REFINING CO.
 Farm- Earl W. Campbell No. 1

SEC. 7 T. 26 R. 34W
 SW SW SE

Total Depth. 5200'

Comm. 12-20-58


Comp. 1-21-59

Shot or Treated.

Contractor. Sierra Petroleum Co.

Issued. 3-28-59

County Finney
 KANSAS



CASING:

10 3/4" 830' cem w/600 sx.
 5 1/2" 5199 1/2' cem w/900 sx.

Elevation. 3001' GL

Production. 120 BOPD

Figures Indicate Bottom of Formations.

sand & shale	255
sand	310
gravel & sand & shale	405
blue shale & clay	830
sand, shale & red bed	1401
red bed & shale	1895
red bed & anhydrite	2023
gyp & shale	2257
Anhydrite & lime	2527
lime, shale & chalk	2637
lime	2848
lime & shale	3028
lime	3371
lime & shale	3905
lime	4012
lime & shale	4037
lime	4542
shale & lime	4585
lime	4595
lime & shale	4640
lime	4687
lime & sand strks	4730
lime	4845
lime & shale	4926
lime	4936
sand	4962
lime	5200
Total Depth	

TOPS:

Anhydrite	2257
Krider (scout)	2528
Winfield (scout)	2573
Towanda (scout)	2647
Heebner (scout)	3843
Toronto (scout)	3856
Lansing (scout)	3893
Base Kansas City	4429
Marmaton Shale	4450
Cherokee	4600
Atoka	4816
Morrow Shale	4876
Mississippi	4960
St. Louis	5051