


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- **CHAMPLIN OIL & REFINING CO.**
 Farm- **Earl Campbell No. 2**

SEC. **7** T. **26** R. **34W**
 C **SW SW**

Total Depth. **5182'**
 Comm. **2-20-59** Comp. **5-22-59**
 Shot or Treated.
 Contractor.
 Issued. **8-8-59**

County **Finney**
KANSAS



CASING:

10" **830'**
 7" **5181½'**

Elevation. **2998'**

Production. **254 BOPD**

Figures indicate Bottom of Formations.

sand, shale & gyp	725
sand & shale	815
sand, shale & red bed	1635
sand & shale	2330
lime & shale	3019
lime	3580
lime & shale	3700
lime, shale & chalk	3890
lime & chalk	3988
lime	4385
lime & chalk	4440
lime	4945
lime & sand	4954
lime	5104
Mississippi lime	5182
Total Depth	

DST #4 5118-5132/op 2 hrs, weak blow increased gradually to good blow in 20 min. and for remainder of test, rec. 1470' gas in drill pipe, 225' free oil, 90' O & GCM, 60' Sli O & GCM, 30' watery mud ISIP 1325#/30" IFP 30#, FSIP 1235#/60" FFP 175#, Hydro Press. 2700#-2650#.

DST #5 5160-82', op 2 hrs., covering Zone "C". Weak blow and died in 28 min. Dead remainder of test. Rec. 40' drlg. mud, IFP 30#, FFP 30#, ISIP 55#/30", FSIP 840#/60", Hydro Press. 2750# - 2730#.

TOPS:

Krider (scout)	2518
Winfield (scout)	2574
Heebner	3844
Toronto	3860
Lansing-Kansas City	3890
Base Kansas City	4434
Marmaton	4448
Cherokee	4600
Atoka (?)	4822
Morrow Shale	4884
Morrow Ls	4914
Morrow Ls	4934
Morrow Sd	4955
St. Gen	4968
St. Louis	5059
"Zone B	5120

DST #1 4897-4954', packers failed.

DST #2 4885-4954', packers failed.

DST #3 4870-4954', op 2 hrs., fair blow thruout, rec. 697' fluid; 46' HGCM, 201' HG & OCM, 210' muddy oil, 60' free oil, 180' OCM, Hydro. Press. 2580#-2580# ISIP 1355#/30" IFP 115#, FSIP 1305#/60" FFP 295#.