


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- CHAMPLIN OIL & REFINING CO.
Farm- C. Lee Reeve No. 2

SEC. 7 T. 26 R. 34W
C NE NW

Total Depth. 5216'
Comm. 6-4-59 Comp. 9-29-59
Shot or Treated.
Contractor.
Issued. 12-5-59

County Finney
KANSAS



CASING:

10" 844'
7" 5213½'

Elevation. 2999' DF

Production. 347 BOPD

Figures indicate Bottom of Formations.

sand 417
sand & lime 700
lime & shale 850
red bed & shells 2310
shells & shale 2389
shale 2416
Anhydrite 2550
Anhydrite & shale 2787
Anhydrite & shale & lime 2897
sandy lime & shale 2977
lime & shale 3080
shale lime chalk 3284
lime & shale 3401
lime, chalky lime & shale 3485
lime & shale 3614
lime, chalky lime & shale 3714
lime 3744
lime, chalky lime & shale 3957
lime & shale 4047
lime 4078
lime & chalky lime 4178
lime 4209
lime & shale 4296
lime 4906
lime & shale 4997
lime 5057
sandy lime 5108
lime 5216 RTD
Total Depth

DST #3 5158-5216', op 2 hrs., wery weak blow initially. Rec. 110' drilling mud, slightly gas cut. ISIP 1260#/30", FSIP 760#/60". IFP 40#, FFP 105#.

DST #1 4890-4997' op 2 hrs., weak to very weak blow thruout test. Rec. 90' drilling mud, and 455' heavy gas cut drilling mud w/dark oil stain. IFP 200#, FFP 340#, ISIP 1320#/30", FSIP 1320#/60".

DST #2 5086-5117' op 2 hrs., strong to weak blow thruout test, gas to surf. in 40 mins. (TSTM). Rec. 2850' fluid consisting of 2400' gassy oil, 180' mud & gas cut oil 270' heavy oil & gas cut mud. IFP 151#, FFP 725#, ISIP 1240#/30", FSIP 1107#/60".

TOPS: LOG

Heebner 3850
Toronto 3864
Lansing-Kansas City 3896
Base Kansas City 4466
Marmaton 4484
Cherokee 4623
Atoka 4836
Morrow 4902
Morrow Lime 4931
Morrow Sand 5015
St. Genevieve 5041
St. Louis 5087
" " Zone A 5088
" " Zone B 5165
" " Zone C 5197