

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk Bldg. Wichita, Kansas

8-26-34W


Company - WHITE EAGLE OIL COMPANY  
Farm - Bedford No. 2

SEC. 8 T. 26 R. 34W  
NE NE SW

Total Depth. 2710  
Comm. 2-13-48 Comp. 3-27-48  
Shot or Treated.  
Contractor.  
Issued. 6-12-48

County, Finney

KANSAS



Elevation. 2983 feet.

Production. 25,375,000 gas

CASING:

10 3/4" 618' cem. 400 sx.  
7" 2533' cem. 750 sx.

Figures Indicate Bottom of Formations.

sand, yellow clay & gyp	450
blue shale, red rock	647
red bed	1000
red bed & gyp	1235
red bed & anhydrite	1375
red bed & shale	1700
shale, red rock & lime	1920
lime & anhydrite	2310
lime	2437
lime & shale	2563
lime	2575
lime, broken lime & shale	2606
lime & broken lime	2646
lime & shale	2687
lime	2710
Total Depth.	

TOPS:

cimarron anhydrite	1920-2020
Wellington	2240-2530
Hollenberg	2470-2480
Herington	2530-2538
Krider	2536-2536
Winfield	2561-2597
Upper Fort Riley	2630-2667
Lower Fort Riley	2680-2710