

16-26-34W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- CHAMPLIN OIL & REFINING CO.
Farm-Frederick A. Stone No. 1

SEC. 16 T. 26 R.34W
C SW SW

Total Depth. 5173'
Comm. 1-1-61 Comp. 1-20-61
Shot or Treated.
Contractor. H & H Drlg.
Issued. 4-15-61

County Finney
KANSAS



CASING:
9" 848'
7" 5169'

Elevation. 2961'

Production. 65 BOPD

Figures Indicate Bottom of Formations.

| | |
|----------------------|------|
| ○ sand, water gravel | 219 |
| ○ sand & gravel | 360 |
| shale | 515 |
| red bed & shells | 745 |
| red bed & shale | 848 |
| shale & lime | 915 |
| red bed | 1210 |
| shale | 1520 |
| sand & shale | 1800 |
| shale | 1880 |
| Anhydrite | 1965 |
| Anhydrite & shale | 2238 |
| shale & lime | 3540 |
| shale, lime & chalk | 3545 |
| shale & chalk | 3635 |
| shale, lime & chalk | 3709 |
| chalky lime | 3815 |
| ○ shale & lime | 3921 |
| lime | 4021 |
| lime & shale | 4044 |
| lime | 4190 |
| lime & chalk | 4270 |
| lime | 5173 |
| Total Depth | |

| | |
|--------------|------|
| TOPS: SCOUT | |
| Lansing | 3887 |
| Marmaton | 4460 |
| Cherokee | 4588 |
| Morrow | 4862 |
| St. Geneieve | 4947 |
| St. Louis | 5018 |