

16-26-34W


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

Company - CHAMPLIN REFINING CO.
Farm - Nolan No. 1

SEC. 16 T. 26 R. 34W
NE NE S.
2310' fr WL, 2310' fr
SL of SW/4

Total Depth. 2734'
Comm. 9-15-48 Comp. 10-27-48
Shot or Treated.
Contractor.
Issued. 11-20-48

County. Finney
KANSAS



CASING:

8 5/8" 540' cem w/300 sx.
5 1/2" 2729' cem w/641 sx.

Elevation. 2967 Ind

Production. 15,000,000 gas

Figures Indicate Bottom of Formations.

sand	30
sand and shale	548
sh lo	690
red bed	825
shale and sand	920
red rock & shells	1175
redrock & shale, anhy.	1360
shale and sand	1615
redrock, shale, anhyd.	1815
redrock & anhyd.	2320
gyp and anhydrite	2595
gyp and lime	2630
shale	2665
lime brkn	2734
total depth	

Tops:

Hollenberg	2488
Herrington	2514
Krider	2550
Winfield	2586
Towanda	2632
Ft. Riley	2684