

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

17-26-34W


Company - HELMERICH & PAYNE, INC.
Farm - Yeiser No. 1

SEC. 17 T. 26 R. 34 W
Center of Section

Total Depth. 2695'
Comm. 12-20-44
Shot or Treated.
Contractor.
Issued. 7-28-45

Comp. 3-3-45

County. Finney
KANSAS



CASING:

10 3/4" 757' Cem.
5 1/2" 2693' Cem.

Elevation. _____

Production. 10,860,000 G.

Figures Indicate Bottom of Formations.

shale	0-90
gravel	115
shale & shells	240
gravel	270
shale & shells	550
shale blk	610
clay	635
shale sticky	687
shale, gyp, shells	743
shale red, shells	757
red bed	1140
shale	1270
anhydrite	1380
red bed	1430
salt & sand	1560
shale	1650
red bed	1875
lime	1940
sand, hrd	1970
shale sticky	2070
sand	2075
shale sticky	2135
shale	2200
lime, anhydrite	2255
lime	2335
anhydrite	2450
anhydrite, lime	2477
lime hrd	2635
shale	2695
Total Depth	