

WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

19-26-34W

Company - HOWARD KUHN
Farm - Devlin

No. 1


SEC. 19 T. 26 R. 34W
SEC NW

Total Depth. 2660'
Comm. 5-5-47
Shot or Treated. Acid.
Contractor.
Issued. 8-30-47

Comp. 6-30-47

County. Finney

KANSAS



Elevation. 2981' act. & pk.

Production. 23,738,000 Gas

Figures Indicate Bottom of Formations.

10 3/4" OD	600'	
7" OD	2485'	com. w/325 sx.
○ sand & gravel	0-425	
○ sand & shale	485	
○ sand	517	
○ shale	546	
○ sand	612	
○ shale & sand	819	
○ red bed	1290	
○ lime brkn & shale	1325	
○ shale	1392	
○ sand	1574	
○ shale	1865	
○ shale & shells	2035	
○ shale & sand	2167	
○ shale	2295	
○ lime & shale	2395	
○ anhydrite	2479	
○ lime	2495	
○ lime	2500	
○ shale	2503	
○ lime	2555	
○ (First Gas @ 2518')		
○ (Second Gas @ 2544')		
○ shale	2564	
○ lime	2618	(Gas in Top @ 2564)
○ red bed	2637	
○ lime	2660	(Gas from 2638-2658)
Total Depth		

Treated first to gas pays with 3,000 gal.
before drilling deeper, increased from
70,000 to 3,500,000. completion of
drilling Acidized second treatment with
3,000 gal. Third treatment with 14,000 gal.
Washed with 1,000 gal. of 7½ % acid.
Well gauged 23,738 MCF on 20 min. blow down.
Set line. (Every joint is perforated)