

19-26-34W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- McKNAB-LINDSAY
Farm- Kuhn-Devlin No. 7

SEC. 19 T. 26 R. 34W
C NE NE

Total Depth. 5191'
Comm. 9-8-58 Comp. 10-1-58
Shot or Treated.
Contractor. McKnab-Lindsay
Issued. 3-21-59

County Finney
KANSAS



Elevation. 3000'

Production. 140 BOPD

CASING:

8 5/8" 836' cem w/450 sx.

5 1/2" 5191' cem w/200 sx.

D-V tool set at 2821 w/200 sks cem.

Figures Indicate Bottom of Formations.

sand	98
shale, sand & gyp	605
shale & lime	820
red bed	838
red bed & sand	1830
red bed & anhydrite	1935
shale	2370
shale & silt	2450
lime & shale	3180
lime	3265
lime & shale	3422
lime	3585
lime & shale	3700
lime	4920
shale	4925
lime & shale	4996
lime	5191
Total Depth	

TOPS: SCOUT

Ruebner	3882
Toronto	3896
Lansing	3932
Marmaton	4497
Atoka	4857
Morrow Form.	4918
St. Geneieve	4992
St. Louis	5073
Mississippi "B"	5084
Mississippi "C"	5137
Mississippi "D"	5176